

Plot 3 + 4 Combined

4,000 m² · Parcel 96 · Basin Al-Zara North (7) · Makawir

Dhiban District · Madaba Governorate · Hashemite Kingdom of Jordan

1,080 m²

MAX FOOTPRINT · 27% coverage

2,700 m²

TOTAL FLOOR AREA · 2 floors +
roof

2 + roof

STOREYS · 9 m height limit

0.675

FLOOR AREA RATIO

This study answers one question — **how much can be built on the combined plot, and in what form** — and then says plainly what stands in the way. It is written from the drawings and the survey you supplied, and from the verified text of **Building and Town & Village Planning Regulation No. (1) of 2022**.

■ THE STUDY RESTS ON ONE UNCERTIFIED ASSUMPTION

Every number above assumes the land is zoned السكن الأخضر الريفي — **Green / Rural Residential**. That is the best reading of the evidence, but **no document in the file states the zoning class** and Jordan publishes no register from which it can be read.

If the certificate returns a different class the footprint moves by a factor of up to 2.7×. **Obtain the كشف أحكام تنظيمية from the Dhiban Directorate of Municipal Affairs before committing to any design.**

Contents — 1 Executive summary · 2 The site · 3 Planning envelope · 4 What you can occupy · 5 Height, levels and the ceiling · 6 Total exploitable area · 7 Design strategy · 8 Yield and parking · 9 Constraints and challenges · 10 Approvals roadmap · 11 Compliance schedule · 12 Basis, limitations and sources

1 · Executive summary

The combined plot gives you 1,080 m² of footprint and 2,700 m² of countable floor area over two storeys and a roof floor. Combining plots 3 and 4 was worth doing — but not for the reason owners usually expect. It buys you a single well-proportioned development parcel and the freedom to place the building on the half of the site that can actually take it. **It buys you no additional height whatsoever.**

Two findings govern everything that follows.

FINDING 1 — the height bonus for a bigger plot does not apply here

Article 16(c) normally grants **+35 cm of height for every 100 m² above the minimum subdivision area**. On a 2,000 m² minimum that would read as a 2,000 m² surplus and **+7.00 m** — and it is exactly the kind of number that gets designed against.

Article 16(e) disapplies paragraphs (b), (c) and (d) for **plots served by roads narrower than 20 m**. This plot is served by a 6 m road and a 10 m street. No height bonus, no high-building table, no additional floor under 16(f) either, which needs a 14 m street. **This holds whatever the zoning class turns out to be.**

FINDING 2 — the topography, not the coverage, is the design problem

The site falls about **15 m across its 47 m width — roughly 25%, one in four** — and it falls east to west, across the short dimension, with **no road on either the high or the low side**. Measured from the 10 m street the 9 m limit becomes a **flat ceiling at roughly +15.0**, and the natural ground at the north-east corner is **already at +15.0**.

So the height available above natural ground runs from 15 m at the south-west corner to **zero at the north-east corner**. A conventional block on the upper half of this plot cannot be built. The scheme has to step.

And one asset that is easy to miss:

THE SLOPE FALLS TOWARD THE VIEW


The ground falls **west — straight toward the Dead Sea, 2.0 km away**. The site's topographic problem and its commercial asset are the same feature. A terraced scheme stepping down westward gives **every unit an unobstructed sea view over the roof of the one below**, and the regulation pushes you in precisely that direction: you are given 1,080 m² of footprint inside a 2,420 m² envelope and forbidden to go up. **Spread out, step down, face west.**

The headline schedule

Measure	Value	Control
Plot area (registered)	4,000 m²	Approved area schedule, stamped 25/4/2026
Buildable envelope after setbacks	2,420 m²	8 m front (both streets) / 6 m sides
Maximum footprint	1,080 m²	Art. 16(a) — coverage 27%
Envelope actually used	45%	coverage binds, not geometry
Ground floor	1,080 m²	at full coverage
First floor	1,080 m²	at full coverage
Roof floor (الروف)	540 m²	Art. 48(a) — ≤ 50% of the floor below
Total countable floor area	2,700 m²	المساحة الطابقية
Floor area ratio	0.675	derived
Basement — terraced, not habitable	≈ 2,428 m²	excluded from coverage AND floor area
Total constructed area	≈ 5,128 m²	including the basement
Minimum landscaped area	400 m²	Art. 16(a) — 10%
Storeys	2 + roof floor	Art. 16(a)
Height limit	9.00 m excluding the roof floor	Art. 16(a)

2 · The site

The plot is the western pair of a four-plot subdivision of parcel 96, merged into a single 4,000 m² holding. It is a long north–south trapezoid with a street at each end and private land along both flanks.



Site plan — dimensions as printed on the approved subdivision plan; spot levels read from the topographic survey of 13-6-2026 (local datum). The eight rectangles are indicative only: they show what 27% coverage looks like distributed as terraced units, not a proposal. Schematic — not a survey drawing.

Geometry and boundaries

Boundary	Length	Abuts	Consequence
North	47.26 m	طريق 6 متر — 6 m road	Front setback. Under 8 m, so excluded from the height datum (Art. 15(a)(1)).
South	47.88 m	شارع 10 متر — 10 m street	Front setback. The sole road that sets the height datum.
West	86.27 m	Parcel 321 — private	Side setback. The low side and the view side.
East	82.23 m	Plots 1 & 2 — private	Side setback. The high side, where the ceiling bites.

Verification — the coordinate schedule on the plan shoelaces to 9,236.03 m² against the printed total of 9,236.720 m², an agreement of 0.007%. Re-drawing the merged plot from its four printed dimensions returns 4,000 m² against the scheduled 4,000 m². **The plan is internally consistent and the geometry can be relied on.**

Position, elevation and setting

Item	Value	Note
Position	31.5995° N 35.5659° E	Palestine Grid (Cassini) → WGS84, from the plan's own coordinates
Elevation	−226 m to −361 m	SRTM 30 m, sampled across the parcel — below sea level
Dead Sea shore	≈ 2.0 km west	the downhill direction
Zarqa Ma'in springs	≈ 2.4 km	
Machaerus / قلعة مكاور	≈ 6.6 km	archaeological setting — see §9
Statutory status	inside the Jordan Valley	Jordan Valley Development Law — hence the JVA seal

The independent elevation model shows a fall of the same order and direction as the surveyor's contours. **The 25% gradient is corroborated, not merely asserted.**

3 · The planning envelope

Setbacks for Green / Rural Residential are **8 m front, 6 m side, 6 m rear**. Because the plot fronts a street at each end, the conservative reading — and the one this study adopts — is that **both ends take the 8 m front setback** and the two private flanks take 6 m.

Case	Setbacks applied	Envelope	Footprint permitted	Envelope used
A — adopted both streets treated as front	8 / 6 / 6 / 8	2,420 m²	1,080 m ²	45%
B — upside 6 m road treated as rear	8 / 6 / 6 / 6	2,490 m ²	1,080 m ²	43%

The coverage cap binds — the geometry does not

The envelope is roughly **68 m × 36 m** $\approx$ **2,420 m²**, but you may only cover **1,080 m²** of it. You are therefore using **45%** of the room you have.

On a flat site that would be a constraint. **On a 25% slope it is a gift** — it is exactly the latitude a terraced scheme needs to spread along the contours instead of cutting across them. Which of case A or B applies changes the envelope by 3% and changes nothing you can build.


Confirm case A with the Committee in writing — it is a question of practice, not of text.

If more footprint is needed — Article 16(g)

The Council may approve a building **without being bound by the coverage percentage**, provided complete plans for the whole building are submitted and the floor-area ratio and setbacks are respected. On a steep site this is worth pursuing: it lets you trade height you cannot use for footprint you can, which is the right trade here. Treat it as an application to be argued, not an entitlement.

4 · What you can occupy

What the 4,000 m² actually yields



From title to buildable: the setbacks take 40% of the plot, and the coverage rule then limits you to 27% of the title area — under half the envelope the setbacks left.

Area schedule

Component	Area	Counts toward coverage	Counts toward floor area	Authority
Ground floor	1,080 m ²	Yes	Yes	Art. 16(a)
First floor	1,080 m ²	—	Yes	Art. 16(a)
Roof floor الروف	540 m ²	—	Yes	Art. 48(a)
Countable total	2,700 m²			المساحة الطابقية
Basement قبو	≈ 2,428 m ²	No	No	Art. 2 definitions
Parking	as designed	No	No	Art. 2 / 36(b)(5)
Setback decks	as designed	—	No	Art. 33(d)(5)
Mechanical services floor	as designed	—	—	Art. 15(e) — outside height & floor count
Ancillary building	≤ 25 m ²	No — additional	—	Art. 34(a)
Landscaped area (minimum)	400 m ²	—	—	Art. 16(a) — 10%

The exclusions are where the real capacity of this site sits. A قبو is by definition below natural ground on every side, may occupy **the entire plot except the front setback**, and is excluded from both the coverage percentage and the floor area. On a plot with 15 m of fall that is a very large volume of free space — provided it is detailed as a basement and not as a semi-basement. §6 quantifies it.

5 · Height, levels and the ceiling


This is the part of the study that most changes what can be drawn.

How the datum is established

Article 15(a)(1) measures height from the **average of the levels of the adjoining roads**, and expressly **disregards roads narrower than 8 m**. The 6 m road on the north therefore drops out. The 10 m street on the south survives — the plot fronts 100% of that side — and Article 15(f) then requires its **average** level to be used where the road itself has several levels, which this one certainly does: it runs from about 0.0 at its western end to about 12.0 at its eastern end.

Step	Value	Authority
Height datum (average of the 10 m street)	≈ +6.0	Art. 15(a)(1) and 15(f)
Permitted height	9.00 m	Art. 16(a)
Ceiling — structural top of the 2nd floor	≈ +15.0	derived
Roof floor above that	+3.50 m	Art. 48(a)(2)
Top of roof floor	≈ +18.5	outside the 9 m

Section across the slope — the height limit is a flat ceiling over rising ground



Section across the slope, west (low) to east (high). The 9 m limit is a horizontal line at ≈ +15.0 while the ground climbs to meet it. Terracing is not a stylistic choice here — it is the only way to keep two storeys and a roof floor under that line across the plot.

What the ceiling means corner by corner

Corner	Natural ground	Ceiling	Height available	What binds
SW — 10 m street, west end	≈ 0.0	+15.0	15.0 m	the storey count, not height
NW — 6 m road, west end	≈ +4.5	+15.0	10.5 m	the storey count
SE — east flank, south end	≈ +12.0	+15.0	3.0 m	the ceiling
NE — 6 m road, east end	≈ +15.0	+15.0	0.0 m	unbuildable as measured

The binding constraint flips across the plot

On the **western half** you run out of storeys before you run out of height — there is roughly 6 m of unused headroom under the ceiling.

On the **eastern half** the ceiling arrives first, and at the north-east corner it has already arrived. **Measured from the street datum, you cannot put a building there at all.**

The three reliefs that make the upper half buildable

These are in the regulation. None is discretionary invention; each has a price.

Relief	What it gives	What it costs
Art. 15(c) — measure from natural ground where natural ground is above road level	Height taken from local natural ground instead of the street datum. And the first floor may be used for parking or services and is excluded from both the height and the storey count.	The building may contain no طابق تسوية (semi-basement) anywhere.
Art. 36(b)(4) — ground floor as parking	The ground floor given over to parking is excluded from the permitted height ; up to 25% of it may be building services.	That floor is parking, not saleable area.
Art. 33(d) — deck the setbacks	Decks over the setbacks supporting the street, retaining wall or rock cut. Excluded from total built area and from floor area. Where a plot fronts more than one street the deck may be on the upper street side, the lower, or both.	Deck level must follow the adjoining street and in no case exceed 45 cm; use beneath is restricted to parking and services; an accurate topographic plan must accompany the application.

The design move that unlocks the site


Article 15(c) forfeits the **تسوية (semi-basement)** — but a **قبو (true basement)** is a different creature under the Article 2 definitions and is **not** forfeited.

So: **bury the uphill side as a قبو, never as a تسوية**. The **قبو** is excluded from coverage and from floor area, may run to the plot boundary except in the front setback, carries the parking and the plant — and leaves Article 15(c) intact so the storeys above can be measured from natural ground.

Detail it to the **45 cm** test (concrete surface no more than 45 cm above natural ground or the average road level, whichever is lower) and it is a **قبو**. Let it drift to **1.5 m** above the average road level and it becomes a **تسوية** — and the relief is gone.

That 45 cm is the single most valuable dimension on this project.

6 · Total exploitable area



The countable stack is 2,700 m². The basement sits outside both ratios entirely.

The basement — how much is actually achievable

The legal allowance and the buildable reality are different numbers, and it is worth being honest about the gap.

	Area	Basis
Legal maximum footprint of a قبو	≈ 3,239 m ²	whole plot less the two front setbacks (Art. 2 definition)
Achievable within the building envelope	≈ 2,428 m ²	36 m × 68 m, delivered as 3 terraced steps of ≈ 12 m
Further area available under the side setbacks	≈ 819 m ²	a قبو may occupy the side and rear setbacks

Why it has to be terraced — a single buried level can only span the band over which the ground falls less than one floor-to-floor height. At a 3.0 m structural height and a 25% gradient that band is **12 m wide**. Across a 36 m envelope you therefore need **3 stepped levels**, each following a contour band, to stay within the 45 cm test along its whole perimeter. Anything drawn as one flat basement slab across the full width will fail the definition and be reclassified as a تسوية.

Total constructed area

	Area	Character
Countable floor area (المساحة الطابقية)	2,700 m ²	habitable / saleable
Net of circulation and cores at 12%	≈ 2,376 m ²	indicative net saleable
Terraced basement	≈ 2,428 m ²	parking, tanks, plant, storage — not habitable
Total constructed	≈ 5,128 m²	

Read the basement correctly


Article 38(a) restricts the قبو to **parking, reinforced-concrete water tanks, storage, heating and cooling plant with fuel tanks, and electrical rooms**. It cannot be habitable and cannot be sold as accommodation.

Its value is indirect and considerable: it absorbs all the parking and all the plant, which frees the whole of the 2,700 m² above ground for saleable area, and it does so without consuming a square metre of either ratio.

7 · Design strategy


What the regulation and the ground are jointly telling you to do.

✗ One block across the slope




Needs 9 m of cut and fill.
Setback fill is capped at 1 m.
Blocks the view from behind.

✗ Tall block on the high side over



Ceiling +15 is already at
natural ground here.
No height left to build in.

✓ Terraces stepping with the contours



Each terrace reads the ground it
sits on. Every unit sees west
over the roof below.

west (low) ↔ east (high) ——— red line = the +15.0 ceiling

Three responses to the same section. Only the third survives both the height ceiling and the 1 m cap on fill within the setbacks.

The eight moves

1. Put the mass on the lower, western half.

That is where the ceiling at $\approx +15.0$ leaves real headroom and where the storey count, not the height, is what limits you. The upper third of the plot is better as landscape, parking deck and the 400 m^2 of green area you owe anyway.

2. Run the building north–south and step it east–west.

The contours run north–south; the fall runs east–west. A long, narrow, stepped form parallel to the contours works with the site. A compact block across them fights it and loses.

3. Take the coverage, not the height.

You are permitted $1,080 \text{ m}^2$ of footprint inside a $2,420 \text{ m}^2$ envelope and forbidden to go up. Spread out. If the scheme wants more footprint, Article 16(g) is the route — full plans, floor-area ratio and setbacks respected.

4. Bury the uphill side as a قيو, never as a تسوية.

Excluded from coverage and floor area, may run to the boundary except in the front setback, and preserves the Article 15(c) relief. The 45 cm test governs the detail.

5. Where mass must go on the upper half, take Article 15(c) there.

Measure from natural ground and use the first floor for parking and services so it drops out of both the height and the storey count. This is what converts the eastern half from unbuildable to buildable.

6. Build as several buildings, not one.

Article 15(a)(3) computes each building's height from the **nearest** road where a plot fronts more than one road and carries more than one building. On a 15 m fall a terraced villa scheme can have each unit read the ground it stands on. **This is the strongest structural argument for villas over a single apartment block here.**

7. Deck the setbacks at both street ends.

Article 33(d) recovers usable service area that counts against neither ratio, and handles the level change at the street edge within the 45 cm rule — rather than filling, which is capped at 1 m.

8. Orient everything west.

The fall, the view and the Dead Sea are the same direction. Step the terraces so each unit looks out over the roof of the one below — then shade that west elevation properly (see §9).

8 · Yield and parking

Brief: **multiple villas or apartments for sale or rent**. The Green / Rural zone permits this — Article 47(l) restricts these zones to **residential use and places of worship**, and multi-unit residential sits squarely inside that. **Tourism, chalets, hospitality and retail do not.**

Option A — apartments

Gross area per apartment	Units	Parking required	Basis
120 m ²	22	22	1 per apartment (exceeds the area rate)
150 m ²	18	18	1 per apartment (exceeds the area rate)
180 m ²	15	15	1 per apartment (exceeds the area rate)
200 m ²	13	13	1 per apartment (exceeds the area rate)

On 2,700 m² of countable floor area, less roughly 12% for cores and circulation, about 2,376 m² is net saleable.

Option B — villas

Villas	Footprint each	Gross each (2 floors + roof)	Parking required	Comment
6	180 m ²	450 m ²	9	generous; best terracing rhythm
8	135 m ²	338 m ²	9	the balanced option — ≈13 m × 10.4 m plates
10	108 m ²	270 m ²	10	tighter plates, more repetition
12	90 m ²	225 m ²	12	plates get narrow for a 2-storey villa

Parking — the rule that catches phased schemes

Rate for residential zones including ريفي: **one space per 300 m² of total built area, or one space per apartment — whichever gives the greater number.** Above nine units the per-unit rate always governs here.

Article 36(b)(1): no building may be licensed unless the parking for the FULL permitted building on the plot has been provided — regardless of how much you are licensing now. Under 36(b)(2), if you provide fewer spaces the Committee may licence only the matching area or unit count, and **no further area may ever be licensed.** Design the parking for the whole entitlement on day one even if you build in phases.

Article 36(c): parking is not permitted in the front setback in residential zones. Article 36(d) does allow open parking in the side and rear setbacks, subject to clear width, manoeuvring within the plot, and the front setback being kept clear.

Recommendation. On this section, **8 terraced villas** is the strongest fit. It keeps plates at a workable ≈13 m × 10.4 m, gives a terracing rhythm that suits a 25% gradient, opens Article 15(a)(3) so each unit takes its height from the ground it stands on, needs only 9 parking spaces, and puts every unit on the west elevation with a sea view. An apartment block of 15–18 units yields the same floor area but concentrates it into one mass that has to solve the whole 15 m of fall in a single building — and it needs 15–18 spaces instead of 9.

9 · Constraints and challenges

Set out in order of how badly each can hurt the project. Severity is NORMIA's assessment; the authority column is verified.

CRITICAL Zoning class is not established

No document in the file states the *فئة المنطقة*, and Jordan publishes no register from which it can be read. If the land proves to be outside the zoning boundary, Article 44 applies instead and coverage drops from 27% to **10% — 400 m² instead of 1,080 m²**.

Mitigation. Request the *كشف أحكام تنظيمية* from the Dhiban Directorate before any design spend. Nothing in this study is safe until it is in hand.

CRITICAL The merger is not yet final

The stamped plan carries only a *no objection to proceed after the Committee's approval and payment of the legal fees*, dated 25/4/2026. Until the merger is registered these remain **two separate 2,000 m² parcels** and no single building may be licensed across both.

Mitigation. Complete the Committee approval, pay the fees and register the new title. Also resolve why a four-plot print is dated 15/6/2026, after the merged version was endorsed.

CRITICAL The height ceiling collides with natural ground on the east

Measured from the 10 m street the 9 m limit is a flat line at $\approx +15.0$, and the north-east corner of the plot is already at $+15.0$. **Roughly the eastern third cannot carry a building measured the conventional way.**

Mitigation. Design the scheme terraced on the western half; take Article 15(c) on any mass above the datum; put a written question to the Committee on the datum before design freeze.

HIGH The datum question is unresolved and worth metres

Article 15(a)(1) excludes roads under 8 m; 15(a)(2) provides a fallback where *all* adjoining roads fail. The natural reading drops the 6 m road and leaves the 10 m street alone — but the 6 m road sits on the **high** side, and including it would lift the datum by several metres and change the entire massing.

Mitigation. Obtain the Committee's position **in writing**. This is the single most consequential interpretive question on the site.

HIGH Slope stability and Article 47(s)

Building is prohibited on land that is steeply sloping and liable to collapse or sliding **where the approved zoning plans so designate it**. At 25%, with locally steeper bands on the eastern third, this plot is in the territory the provision contemplates.

Mitigation. Obtain written confirmation that no part of parcel 96 is so designated, and commission a geotechnical and slope-stability investigation regardless — the retaining design needs it and Article 33(d) decking is conditioned on the structure supporting the street, retaining wall or rock cut.

HIGH You cannot regrade your way out of the slope

Article 33(b)(2) caps **fill within the setbacks at 1 m above natural ground**. On a 25% gradient that removes platforming as a strategy — the obvious engineering answer is simply not available.

Mitigation. Terrace, and use Article 33(d) decking as the compliant alternative to fill. Retaining structures are unavoidable; budget them early rather than discovering them at tender.

HIGH Antiquities — the Kallirhoe / عين الزارة landscape

The basin is named after the Herodian spa and its ancient Dead Sea harbour, the waterborne approach to Machaerus, and is under active archaeological survey by ACOR with the Department of Antiquities. The parcel is ≈ 2 km inland, so probably outside any immediate perimeter — but this scheme involves very substantial excavation.

Mitigation. Raise Department of Antiquities clearance **now**. A chance find during basement excavation would stop the job at the worst possible moment.

HIGH**No sewer — and discharge is prohibited**

Article 33(e) obliges the owner to provide water collection wells and expressly **prohibits discharging them to the sewer network, to septic tanks, to soakaways, or to neighbouring land**. Sealed collection pits are required where no network exists. For 8–18 units on a steep site this is a material cost and a real planning constraint.

Mitigation. Confirm the availability of any network with the municipality and the Jordan Valley Authority. Size sealed pits for the full unit count and plan tanker access on a 25% gradient.

MEDIUM**Stormwater from a 25% escarpment**

The area schedule itself allocates land to **الأودية (wadis)**. Runoff across a one-in-four slope, in a flash-flood landscape, is a design problem before it is a drainage problem — and the prohibition above means it cannot simply be pushed onto the neighbour or into a soakaway.

Mitigation. Model the catchment, intercept upslope at the eastern boundary, and integrate the attenuation into the terrace retaining structure rather than bolting it on.

MEDIUM**West orientation — the view and the heat are the same direction**

Every unit will want to face west for the Dead Sea. West is also the afternoon sun, at an elevation of about –300 m where summer temperatures are among the most extreme in Jordan. Unshaded west glazing here is an expensive mistake.

Mitigation. Deep terraces, brise-soleil or overhangs on the west elevation; the roof-floor setback of half the prescribed setbacks (Art. 48(a)(3)) can be exploited as usable shading depth. Comply with the national thermal insulation code.

MEDIUM**Dead Sea atmosphere is aggressive**

High salinity and bromide-laden air 2 km from the shore attacks reinforcement, fixings, external metalwork and plant far faster than inland specification allows for.

Mitigation. Specify corrosion protection deliberately: cover and concrete mix design, stainless or hot-dip galvanised fixings, and protected condenser and plant locations.

MEDIUM**Access on a one-in-four gradient**

Both streets meet the plot at its ends — the flat dimension — while the site falls across its width. Getting vehicles from street level to three terraced basement levels is the hardest plan-making problem here, and Article 36(c) forbids parking in the front setback.

Mitigation. Resolve the ramp strategy at concept stage, not at detail design. Article 33(d)(4) permits ramps and suspended vehicle passages within the setbacks provided their floor level is below natural ground.

MEDIUM**Parking must be built for the full entitlement**

Article 36(b)(1) and (2): the parking for the entire permitted building must exist before **any** licence issues, and under-providing permanently caps what can ever be licensed.

Mitigation. Build the full parking count in phase one, or accept a permanent ceiling on the scheme.

LOW**No balconies or projections over either street**

Article 39 permits no projection where the street is **12 m or less**. Both streets are. Architectural projections of up to 60 cm within the setbacks remain available.

Mitigation. Design terraces and balconies to face **west, inboard** — which is where the view is anyway. No loss in practice.

LOW**Jordan Valley Authority and Development Zone status**

The parcel is inside the statutory Jordan Valley, hence the JVA seal. Evidence indicates it is **not** in the Dead Sea Development Zone — that zone's core is 16 km north and a Development Zone would be licensed by the Development and Free Zones Commission, not by a municipal directorate — but the gazetted boundary is not published.

Mitigation. Obtain written confirmation from both bodies, and confirm no JVA servitude, wadi buffer or water-resource restriction affects the parcel.

10 · Approvals roadmap

#	Action	With whom	Why it is on the critical path
1	Obtain the كشف شهادة أحكام تنظيمية — inside or outside the zoning boundary, and the فئة المنطقة	Directorate of Municipal Affairs, Dhiban District	Everything in this study depends on it. Changes the footprint by up to 2.7×.
2	Complete the merger — Committee approval, fees, registration of the new title	The competent Committee (اللجنة المختصة)	Until registered you own two 2,000 m ² plots and cannot licence one building across them.
3	Confirm the adopted widths of the 6 m road and the 10 m street on the approved zoning plan	Directorate of Municipal Affairs	The 8 m, 12 m, 14 m and 20 m thresholds each gate a different entitlement.
4	Written ruling on the height datum — does the 6 m road enter the average?	The competent Committee	Worth several metres of massing. Settle it before design freeze.
5	Written ruling on whether both street ends take the 8 m front setback	The competent Committee	Changes the envelope by 3%; settles the site plan.
6	Confirm no part of parcel 96 is designated steep or unstable under Art. 47(s)	Directorate of Municipal Affairs	A designation would prohibit building outright.
7	Date of ratification of the zoning plan for this area	Directorate of Municipal Affairs	Art. 16(f) turns on whether it predates 16/1/2018.
8	Antiquities clearance for parcel 96	Department of Antiquities (دائرة الآثار العامة)	Active archaeological landscape; deep excavation proposed.
9	Jordan Valley Authority position — servitudes, wadi buffers, water resources; confirm the municipal licensing route	JVA, Ministry of Water and Irrigation	The seal on the plan is jurisdictional, not a formality.
10	Confirmation that the parcel lies outside the Dead Sea Development Zone	Development and Free Zones Commission	Would change the licensing authority entirely.
11	Geotechnical investigation and slope-stability assessment	Specialist consultant	Required for the retaining design and for Art. 33(d) decking.
12	Confirm sewer, water and power availability; size sealed collection pits	Municipality / JVA / utilities	Art. 33(e) prohibits the usual disposal routes.

11 · Compliance schedule

Every mandatory figure used in this study, traced to the gazette page it was read from. All numeric tables were read visually from the gazette rather than from OCR — Arabic-Indic numeral recognition is not reliable enough to design against.

Article	Provision	Value applied	Gazette p.
Art. 2	Definitions — قبو / تسوية / floor area / coverage	45 cm and 1.5 m tests; basement excluded from coverage and floor area	2–3
Art. 11(a)	Minimum subdivision area and frontage, Green/Rural	2,000 m ² / 30 m — combined plot complies	10
Art. 12(a)	No subdivision or amendment without the Committee	merger pending	11
Art. 13(a)	Relief up to 15% in green / rural / agricultural zones	noted	12
Art. 13(e)(1)	Subdivision road capacity vs plots served	10 m serves 3–10 plots; 6 m serves 1 — layout complies	12
Art. 15(a)(1)	Height datum; roads under 8 m disregarded	6 m road excluded; datum from the 10 m street	14
Art. 15(a)(3)	Multiple buildings — height from the nearest road	strategy move 6	14
Art. 15(c)	Natural-ground datum where ground is above road level	available; forfeits the تسوية	14
Art. 15(d)	Ground slab may be raised max 2 m	2.00 m	14
Art. 15(e)	Mechanical services floor excluded	noted	15
Art. 15(f)	Single road with multiple levels — use the average	applied	15
Art. 16(a)	Development control table, Green/Rural	8/6/6 m · 27% · 2+roof · 9 m · 10% green	15
Art. 16(e)	Exclusion of (b)(c)(d) — roads under 20 m	no height bonus, no high-building table	17
Art. 16(f)	Additional floor requires a 14 m street	not available	17
Art. 16(g)	Council may waive the coverage percentage	relief route	17
Art. 33(b)	Fences 1.5 / 2 m; fill in setbacks max 1 m	applied	31
Art. 33(d)	Setback decking; 45 cm; upper or lower street or both	excluded from built area and floor area	31–32
Art. 33(e)	Water collection; discharge prohibited	sealed pits required	32
Art. 34(a)	Ancillary building	≤ 25 m ² , additional to coverage, ≤ 2.6 m, detached	32
Art. 36(b)	Parking for the full permitted building; GF parking excluded from height	applied	33
Art. 36(c)(d)	No parking in the front setback in residential zones	applied	33
Art. 36(e)	Parking rate, residential incl. ريفي	1 per 300 m ² or 1 per apartment, greater	34
Art. 38(a)	Permitted uses of the قبو	not habitable	27–28
Art. 39	No projection where the street is ≤ 12 m	applied	28

Article	Provision	Value applied	Gazette p.
Art. 44	Outside-zoning control table	the alternative scenario — 10% coverage	41
Art. 47(l)	Green/rural: residential and places of worship only	multi-unit residential complies	45
Art. 47(s)	No building on designated steep or unstable land	to be confirmed	46
Art. 48(a)	Roof floor — $\leq 50\%$, ≤ 3.5 m, half setbacks	applied	46
Art. 48(b)	Front طابق سطح — zones , , , only	not available here	46–47

12 · Basis, limitations and sources

Confidence register

Finding	Status
Site identity, parcel, basin, village, surveyor	VERIFIED — title blocks, both plans
Coordinates cross-checked against the area schedule (9,236.03 vs 9,236.720 m ²)	VERIFIED — computed
Combined area 4,000 m ²	VERIFIED — both area schedules, cross-checked
Boundary lengths 47.26 / 47.88 / 86.27 / 82.23 m	VERIFIED — stamped plan
Adjoining roads 6 m north, 10 m south	VERIFIED — both plans
Relief ≈ 15 m, gradient ≈ 25% east to west	VERIFIED — survey 13-6-2026, corroborated by SRTM
Position and elevation (–226 to –361 m)	VERIFIED — computed and sampled
Art. 16(e) disappplies the height bonuses	VERIFIED — gazette p.17, read visually
All control tables and height provisions	VERIFIED — gazette pp.10, 14, 15, 17, 41, read visually
Zoning classification	UNVERIFIED — OFFICIAL SOURCE REQUIRED
Inside the zoning boundary	Inferred — the file was handled by the municipal directorate, not the JVA's outside-boundary service
Green / Rural as the class	ASSUMPTION — plot-size regularity, road/plot match, municipal routing. مسكن د is not excluded by the evidence
Height datum ≈ +6.0	ASSUMPTION — read off contours; recompute from levelled spot heights
Whether the 6 m road enters the datum	INTERPRETIVE — Committee ruling required
Whether both street ends take the front setback	INTERPRETIVE — Committee ruling required
Art. 47(s) steep-land designation	UNVERIFIED — OFFICIAL SOURCE REQUIRED
Basement area achievable	MODELLED — terracing model at 3.0 m floor-to-floor and 25% gradient
Unit counts and net saleable areas	INDICATIVE — for capacity testing, not a design proposal

Limitations — please read before relying on any number here

This is a **capacity and feasibility study**, not a design and not a planning approval. The massing shown is indicative: it demonstrates what the permitted footprint looks like distributed across the slope, and is not a proposal.

The zoning classification is assumed. Every area figure moves if that assumption fails.

The height datum is read from contours, not from levelled spot heights. It must be recomputed by the surveyor along the 10 m street frontage before it is designed against.

The drawings are schematic, prepared from the dimensions printed on the approved plan. They are not survey drawings and must not be scaled.

Nothing here has been invented. Where a figure could not be verified it is marked UNVERIFIED and no compliant result is claimed for it.

Sources

Regulation. 2022 لسنة 1 رقم 1 — نظام الأبنية وتنظيم المدن والقرى رقم 1 لسنة 2022. Articles 2, 11, 12, 13, 15, 16, 33, 34, 35, 36, 38, 39, 44, 47, 48. As amended by 2025 لسنة 12 رقم 12 النظام المعدل رقم 12 لسنة 2025.

Site documents. Subdivision plan, four plots, printed 15/4/2026 and 15/6/2026. Subdivision plan, three plots with 3 and 4 merged, endorsed by the Directorate of Municipal Affairs for Dhiban District 25/4/2026, bearing the Jordan Valley Authority seal. Topographic survey of natural ground for 96 مؤقت من اصل 3 مؤقت 4, dated 13-6-2026, Eng. Orwah El-Hawawsha Surveying Office, Madaba.

Corroborating sources. Jordan Valley Development Law (jordanianlaw.com); Jordan Valley Authority outside-boundary building permit service (Jordan Government Portal); Department of Lands and Survey mapping portal (maps.dls.gov.jo); Dead Sea Development Zone master plan (Sasaki) and Jordan Free and Development Zones Group; Kallirhoe / 'Ain az-Zara archaeological project (ACOR Jordan); SRTM 30 m elevation via OpenTopoData.

Prepared by NORMIA — AEC Regulatory Intelligence & Compliance Consultant. NORMIA never invents regulations. Where information cannot be verified against an official source it is marked UNVERIFIED, and no compliant result is issued in its place.